

Asphalt material estimate

Enter each section's length and width (ft) and the compacted thickness (in); tons include 10% waste at 145 lb/ft³.

Section	Length (ft)	Width (ft)	Thickness (in)	Area (sq ft)	Tons (+10%)
Driveway	60	12	3	720	14.36
Turnaround	10	20	3	200	3.99
Total				920	18.35